

Floor	Zone / Quadrant	Green: Illumination System (BSL01)	Blue: HVAC Units (BM321)	Red: Other / Workspaces & Plugs (BMT01/BSens)	Total Points
Planta 1	NW (NO)	107	11	57	175
Planta 1	NE	102	5	27	134
Planta 1	SW (SO)	118	15	49	182
Planta 1	SE	96	12	49	157
Subtotal P1	All Zones (incl. 25 exterior lights & 20 bridge lights)	423	43	182	648

Floor	Zone / Quadrant	Green: Illumination System (BSL01)	Blue: HVAC Units (BM321)	Red: Other / Workspaces & Plugs (BMT01/BSens)	Total Points
Planta 2	NW (NO)	135	17	68	220
Planta 2	NE	110	17	46	173
Planta 2	SW (SO)	118	12	49	179
Planta 2	SE	112	14	40	166
Subtotal P2	All Zones (incl. 24 bridge lights & 3 bridge HVAC)	475	60	203	738
Planta 3	Roof / Technical Areas	0	0	0	0

Floor	Zone / Quadrant	Green: Illumination System (BSL01)	Blue: HVAC Units (BM321)	Red: Other / Workspaces & Plugs (BMT01/BSens)	Total Points
TOTAL	Full CeDInt Building	898	103	385	1,386

2. Executive Summary: Linking Spatial Loads to External Features

- **Blue Squares : HVAC Systems (103 units):** Primarily driven by **Madrid meteorological data** (outdoor temperature, solar radiation, humidity). Consumption peaks during summer cooling and winter heating, with a stronger thermal load on South-facing zones (SW, SE) and densely partitioned office floors (Planta 2, which holds 60 HVAC units vs. 43 on Planta 1).
- **Red Rectangles : Workspaces & Plugs (385 units):** Directly tied to the **UPM Academic Calendar and working hours**. Power draw drops to a minimal baseline (standby equipment/servers) at night, on weekends, and during university holidays, spiking strictly during human occupancy. NW is the most workstation-dense quadrant across both floors (57 plugs on P1, 68 on P2).
- **Green Squares : Illumination System (898 nodes):** Governed by a combination of **building opening hours and natural daylight/solar radiation** (plus nighttime schedules for the 25 exterior perimeter lights located on Planta 1).